





International Elbe Forum 2025

Examples of the implementation of flood protection measures in Germany

Patrik Heinzel Thuringian Ministry for the Environment, Energy, Nature Conservation and Forestry Chairman of the LAWA AH small group NHW







- Gera-Langenberg / Weiße Elster - Alarmstufe 2 [240 cm] - Meldebeginn [160 cm] Alarmstufe 3 [280 cm] Alarmstufe 1 [200 cm] — Mittelwasser [47 cm]

01.06

00

8.

22.05

02

2

18.05

20.

26.05

28.05

30.0

05.06

00

5

90

g

80

Source: LaNaServ im Auftrag der TLUG

00

с,

15.06.







Dyke opening on the Helme 28.12.2023 (Source:)





Development of the National Flood Protection Program (NHWSP)



Special Conference of Environment Ministers on September 2, 2013

- Flood events 2002/2006/2010/2013 (2021!)
- enormous damage caused by flooding
- Importance of supra-regional flood protection in the river catchment areas was emphasized(Solidarity principle)
- to strengthen and accelerate implementation, it was decided to draw up a <u>national</u> <u>flood protection program</u>
- including measures with a supra-regional impact
- categories: Controlled flood retention, dike relocation and elimination of weak points
- with special priority and funding
- Federal/state working group on water was commissioned



Joint federal and state funding



Coordination of earmarked funds via KG of the LAWA-AH

- Technical
 - z. B. Nachmeldung über FGG'en
- Budgetary
 - Resource planning
 - Reallocation of funds
 - Outflow of funds
- Organizational
 - Reporting obligations

Januar – März	•Abstimmung und Beschluss •NHWSP-Liste laufendes Jahr •Priorisierungsliste Folgejahr
April – Juli	 Datenerfassung und -auswertung, Erstellung des Berichts an den Haushaltsausschuss des Deutschen Bundestages zur finanziellen Abwicklung des NHWSP
August – September	•Abschätzung Sockelbetrag Folgejahr •Aktualisierung Mittelbedarf für Umschichtung laufendes Jahr •Aktualisierung Mittelbedarf Folgejahr
Oktober – Dezember	 Umsetzung Mittelumschichtung laufendes Jahr Meldung Mittelbedarf Folgejahr an BMEL Vorbereitung Aktualisierung NHWSP-Liste Folgejahr und Priorisierungsliste übernächstes Jahr
	Timeline for the implementation of national flood protection measures via the Special Framework

Plan for Preventive Flood Protection



Scientific support



Large-scale impact analysis for the Danube, Elbe and Rhine(FuE BfG)

- The measures of the federal states in the NHWSP can make a significant large-scale contribution to lowering the crests of floods on the major rivers (measures on tributaries also have a considerable crest-reducing effect).
- both in terms of the overall impact of all NHWSP measures as well as with regard to their individual effects, the NHWSP has a strong supraregional component.
- BfG (Federal Institute of Hydrology) Reports 2047, 2048, 2049



Longitudinal sections of the measure-related water level reduction on the Elbe between the referencestate 2018 and planned state 2027

Thüringen



Scientific support

synergies of the NHWSP with nature conservation, water ecology and climate policy objectives(FuE BfN)

- extension of the LAWA criteria to expand synergies
 - biodiversity
 - tourism
 - nature and landscape-friendly agriculture and forestry
- BfN-Schrift 638













Latest:

- 36 individual and combined measures to relocate dikes and restore natural retention areas(DRV)
- 61 individual and combined measures for controlled flood retention (HWR) – essentially flood polders and flood retention basins
- 16 individual and combined measures to eliminate weak points(SSB)
- in total, these are 245 individual and partial measures (thereof 168 so-called spatial measures (DRV, HWR))



Ministerium für Umwelt, Energie, Naturschutz und Forsten





Area distribution of the DRV category measures reported in the NHWSP to / in the Danube, Elbe, Oder, Rhine and Weser river basins (as at 2024)

Volume shares of the measures newly created in the NHWSP in the HWR category (right-hand diagram) in the Danube, Elbe, Oder, Rhine and Weser river basins (as at 2024)

Thüringen



Maßnahmenliste 2025 Flussgebietsbezogene Kosten in den Planungszyklen der HWRM-RL

FGG	Maßnahmenkategorie	Kosten in Mio. Euro				
		2015-2021	2022-2027	2028-2033	nach 2033	Gesamt pro FGG
	Deichrückverlegung	102	114	338	84	637
Rhein	Hochwasserrückhalt	271	412	982	362	2.028
	Schwachstellenbeseitigung	182	217	143	152	694
	Gesamt	554	743	1.463	598	3.358
	Deichrückverlegung	51	165	212	59	488
Donau	Hochwasserrückhalt	122	145	302	310	880
	Schwachstellenbeseitigung	247	295	37	0	578
	Gesamt	420	605	551	369	1.945
Weser	Hochwasserrückhalt	0	1	10	0	12
	Schwachstellenbeseitigung	0	2	2	0	4
	Gesamt	0	3	12	0	16
	Deichrückverlegung	102	79	162	678	1.020
Elbe	Hochwasserrückhalt	47	178	217	653	1.096
	Schwachstellenbeseitigung	87	72	54	5	218
	Gesamt	237	329	433	1.335	2.334
Oder	Hochwasserrückhalt	1	0	0	40	41
	Gesamt	1	0	0	40	41
Gesamt		1.213	1.680	2.459	2.342	7.694

List of measures 2025: River basin-related costs in the planning cycles of the HWRM-RL (as at: 02.12.2024)

Latest:

2022-2027:

- Increasing the total volume through further measures
- from 6,2 Mrd. € to 7,7 Mrd. €
- → plus of 1,1 Mrd. €
- NHWSP-Federal funding requirements 2026 amounts 107.345.745 Euro



Energie, Naturschutz und Forsten

Overview of the current implementation status of the spatial measures reported in the NHWSP





Particularly challenging to implement due to the size of the projects!!!

- geopolitical
- Communication
- lack of skilled workers
- long approval procedures
- lawsuits
- high space requirement
- Compensation
- Construction price increases



Ministerium für Umwelt, Energie, Naturschutz und Forsten

Measures in the Elbe River Basin Community



- 37 dyke relocation measures
- 22 flood retention measures
- 6 weak point elimination measures
- completed measures:
 - Elbe_ST_DRV_02701 Altjeßnitz (Mulde-km 34-31)
 - Elbe_BB_HWR_08202 Optimization of the Havel and Spree dam regime for flood retention (measure from Brandenburg und Berlin)
- total costs = 2,334 Mrd. €
 - dyke relocation → 1,02 Mrd. €
 - flood retention → 1,096 Mrd. €
 - weak point elimination → 218 Mio. €



Ministerium für Umwelt,

Freistaat

Relocation of Boizenburg harbor dike and Elbe dike, new construction of Sudesperrwerk (MV)

occasion:

- new maximum water levels measured during floods in 2006, 2011, 2013,
- exceeding the water level by 6 cm, 10 cm and 52 cm,
- the redefinition of design flow rates and the water level required an expansion of the existing flood protection systems.
- Existing dam not structurally capable of sweeping new water level, therefore new construction required

aim:

- improvement of flood protection for the Boizenburg area
- enlargement of the retention area in the Sude to protect the upstream villages in Mecklenburg-Vorpommern and Lower Saxony
- ecological enhancem
- ent of the biosphere reserve area

data and facts:

- reclamation of 124 ha of retention areas in Mecklenburg-Vorpommern and Lower Saxony
- planned start of construction \rightarrow 2026
- end of construction \rightarrow expected 2029

costs:

total: circa 35 Mio. €

• 2025 → circa 900 T€







Ministerium für Umwelt,

Energie, Naturschutz

und Forsten

Thüringen 🚼



Polder Axien-Mauken (S⊤)

occasion:

- project area particularly affected by flooding due to geographical location in the former Elbe floodplain
- dike breaches in the past → flooding of large areas

aim:

 reduction Elbe water level by 20-30 cm in the region and forecast over the entire course of the Elbe up to the state border of Lower Saxony

data and facts:

- 1,694 ha with a volume 52 million m³
- start of construction \rightarrow expected ab 2030
- end of construction \rightarrow expected 2045-2050

costs:

- total: 104 Mio. €
- 2025 → circa 3,3 Mio. €

Area of Action Polder Axien-Mauken





Site map Polder Axien-Mauken

Patrick Heinzel (Obmann LAWA-AH KG NHWSP)







Polder Löbnitz, Vereinigte Mulde (SN)

occasion:

- flood event 2002, extensive flooding + extremely high damage
- flood protection system too close to the water + constricted flood discharge area

aim:

- controlled flood retention
- Reduction of flood crest in the event of crest capping circa 70 cm (for a flood frequency of 100 years)

data and facts:

- Retention volume/retention space with a volume of 15 Mio. m³ for a flood frequency of 25 years / 1.436 ha area ^{Outlet construction}
- start of construction \rightarrow 2013
- end of construction \rightarrow 2029

costs:

- total: circa 53 Mio. €
- *Source: Landestalsperrenverwaltung Sachsen, • 2025 \rightarrow 7,72 Mio. \in (subject to provisional budget management)





Betrieb Elbe/Mulde/Untere Weiße Elster



Siel ferry lock *





Dyke relocation northern Gera-Aue (TH)

occasion:

- altered watercourse structure with unsatisfactory ecological potential
- Dykes too close to the water + constricted drainage cross-section

aim:

- ecological enhancement of the watercourse
- rainage of frequent flood events(for a flood frequency of 20 years)

data and facts:

- reclamation of 840 ha of recent floodplain
- start of construction \rightarrow 2015
- end of construction \rightarrow 2038

costs:

- total: 63 Mio. €
- 2025 → 1,95 Mio. €





Dike relocation and watercourse structuring near Walschleben, 04/2020 (Source: Y.Voigt, ThLG)









Thanks a lot!

10 Jahre Nationales Hochwasserschutzprogramm (NHWSP)

Bericht Hochwasserschutz und Hydrologie

Grundlagen und Umsetzungsstand



lai 2023

LAWA Bund/Länder-Arbeitsgemeinschaft Wasser